## **ADDENDUM #4- Issued 5/23/14**

CITY OF TORRANCE 3031 Torrance Blvd. Torrance, CA 90503

B2014-22

## **Bid for Pueblo Park Improvements**

## ADDENDUM #4

THE FOLLOWING CHANGES ARE HEREBY INCORPORATED INTO AND MADE A MANDATORY PART OF SUBJECT BID:

The bid opening remains **Wednesday**, **May 28<sup>st</sup> at 3:00 PM** in the City Clerk's office.

R	ם(	F٠	9	h	ee	٦ŧ	1 _1	и	D	n
ľ	$\sim$	١.	$\mathbf{\circ}$	ш	-	7 L		ı١	J	u

- Min. 3½" thick natural gray concrete paving. Concrete to have a broom finish with the direction of the broom perpendicular to the flow of traffic, Scorlines to be sawcut per plan. For steel reinforcement, concrete thickness, strength and subgrade preparation, the contractor shall obtain recommendations from a geotechnical engineer.
- Min. 6" thick natural gray vehicular concrete paving. Concrete to have a broom finish with the direction of the broom perpendicular to the flow of traffic, Scorlines to be sawcut per plan. For steel reinforcement, concrete thickness, strength and subgrade preparation, the contractor shall obtain recommendations from a geotechnical engineer.
- Min. 3½" thick natural gray concrete in-fill paving and jacent to existing walkway. Concrete finish shall match adjacent sidewalk paving. Scorelines to continue through and match from existing sidewalk and For steel reinforcement, concrete thickness, strength and subgrade preparation, the contractor shall obtain recommendations from a geotechnical engineer.

Geotechnical recommendations as noted in sheet L-100.

#1: Minimum 4" thick concrete with #3 bars at 24" o.c. both ways at mid height. Pre-saturate and compact subgrade to 90% prior to placing concrete.

#2: Minimum 6" thick concrete with 8"x8" thickened edge below slab where exposed to landscape. Reinforce with #4 rebar @ 18" o.c. both ways at mid height. Pre-saturate and compact subgrade to 90% prior to placing concrete.

#3: Minimum 4" thick concrete with #3 bars at 24" o.c. both ways at mid height. Pre-saturate and compact subgrade to 90% prior to placing concrete. Dowel #3 bars into existing sidewalk at 24"o.c.

## Please return this addendum with your bid proposal.

I hereby acknowledge receipt of this addendum.

Name of Company									
Addre	ss								
City	State	Zip Code							