

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
BASE BID SCHEDULE A												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
1	1	LS	MOBILIZATION	9-3.4	\$ 25,000.00	\$ 25,000.00	\$ 10,000.00	\$ 10,000.00	\$ 27,500.00	\$ 27,500.00	\$ 20,000.00	\$ 20,000.00
2	1	LS	TRAFFIC CONTROL	7-10	\$ 19,000.00	\$ 19,000.00	\$ 5,000.00	\$ 5,000.00	\$ 15,000.00	\$ 15,000.00	\$ 10,000.00	\$ 10,000.00
3	1	LS	BEST MANAGEMENT PRACTICES	7-8.6.2	\$ 5,000.00	\$ 5,000.00	\$ 2,500.00	\$ 2,500.00	\$ 2,500.00	\$ 2,500.00	\$ 6,500.00	\$ 6,500.00
4	930	LF	INSTALL LINER IN 8 INCH VCP SEWER ON PASEO DE GRANADA FROM MANHOLE 92-6-21 TO MANHOLE 101-2-01, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg#23 & 26)	\$ 25.00	\$ 23,250.00	\$ 30.50	\$ 28,365.00	\$ 30.00	\$ 27,900.00	\$ 26.50	\$ 24,645.00
5	26	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON PASEO DE GRANADA BETWEEN MANHOLE 92-6-21 TO MANHOLE 101-2-01	500-1.1.7(a) (Appendix V, Dwg# 23 & 26)	\$ 50.00	\$ 1,300.00	\$ 25.00	\$ 650.00	\$ 50.00	\$ 1,300.00	\$ 50.00	\$ 1,300.00
6	1001	LF	INSTALL LINER IN 8 INCH VCP SEWER ON CALLE MIRAMAR FROM MANHOLE 93-4-08 TO MANHOLE 92-6-08, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 50, 53 & 56)	\$ 25.00	\$ 25,025.00	\$ 30.50	\$ 30,530.50	\$ 30.00	\$ 30,030.00	\$ 26.50	\$ 26,526.50
7	16	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON CALLE MIRAMAR BETWEEN MANHOLE 93-4-08 TO MANHOLE 92-6-08	500-1.1.7(a) (Appendix V, Dwg# 50, 53 & 56)	\$ 50.00	\$ 800.00	\$ 25.00	\$ 400.00	\$ 50.00	\$ 800.00	\$ 50.00	\$ 800.00
8	356	LF	INSTALL LINER IN 8 INCH VCP SEWER ON VIA ALAMEDA FROM MANHOLE 101-1-13 TO MANHOLE 101-1-05, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 16)	\$ 25.00	\$ 8,900.00	\$ 30.50	\$ 10,858.00	\$ 34.00	\$ 12,104.00	\$ 26.50	\$ 9,434.00
9	9	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON VIA ALAMEDA BETWEEN MANHOLE 101-1-13 TO MANHOLE 101-1-05	500-1.1.7(a) (Appendix V, Dwg# 16)	\$ 50.00	\$ 450.00	\$ 25.00	\$ 225.00	\$ 50.00	\$ 450.00	\$ 50.00	\$ 450.00
10	3050	LF	INSTALL LINER IN 8 INCH VCP SEWER ON VIA PASQUAL FROM MANHOLE 101-3-04 TO MANHOLE 91-6-10, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 1, 4, 6, 9 & 13)	\$ 25.00	\$ 76,250.00	\$ 30.50	\$ 93,025.00	\$ 29.00	\$ 88,450.00	\$ 26.50	\$ 80,825.00
11	72	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON VIA PASQUAL BETWEEN MANHOLE 101-3-04 TO MANHOLE 91-6-10	500-1.1.7(a) (Appendix V, Dwg# 1, 4, 6, 9 & 13)	\$ 50.00	\$ 3,600.00	\$ 25.00	\$ 1,800.00	\$ 50.00	\$ 3,600.00	\$ 50.00	\$ 3,600.00
12	1792	LF	INSTALL LINER IN 8 INCH VCP SEWER ON VIA MONTE D'ORO FROM MANHOLE 92-5-31 TO MANHOLE 92-1-15, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 9, 31, 34, 38, 41 & 42)	\$ 25.00	\$ 44,800.00	\$ 30.50	\$ 54,656.00	\$ 29.00	\$ 51,968.00	\$ 26.50	\$ 47,488.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
BASE BID SCHEDULE A					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
13	35	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON VIA MONTE D'ORO BETWEEN MANHOLE 92-5-31 TO MANHOLE 92-1-15	500-1.1.7(a) (Appendix V, Dwg# 9, 31, 34, 38, 41 & 42)	\$ 50.00	\$ 1,750.00	\$ 25.00	\$ 875.00	\$ 50.00	\$ 1,750.00	\$ 50.00	\$ 1,750.00
14	1403	LF	INSTALL LINER IN 8 INCH VCP SEWER ON CALLE DE MADRID FROM MANHOLE 102-1-08 TO MANHOLE 92-6-18, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 64, 68 & 71)	\$ 25.00	\$ 35,075.00	\$ 30.50	\$ 42,791.50	\$ 29.00	\$ 40,687.00	\$ 26.50	\$ 37,179.50
15	45	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON CALLE DE MADRID BETWEEN MANHOLE 102-1-08 TO MANHOLE 92-6-18	500-1.1.7(a) (Appendix V, Dwg# 64, 68 & 71)	\$ 50.00	\$ 2,250.00	\$ 25.00	\$ 1,125.00	\$ 50.00	\$ 2,250.00	\$ 50.00	\$ 2,250.00
16	200	LF	INSTALL LINER IN 8 INCH VCP SEWER ON VIA LOS MIRADORES FROM MANHOLE 92-4-08 TO MANHOLE 91-6-11, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 48)	\$ 25.00	\$ 5,000.00	\$ 30.50	\$ 6,100.00	\$ 35.00	\$ 7,000.00	\$ 26.50	\$ 5,300.00
17	7	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON VIA LOS MIRADORES BETWEEN MANHOLE 92-4-08 TO MANHOLE 91-6-11	500-1.1.7(a) (Appendix V, Dwg# 48)	\$ 50.00	\$ 350.00	\$ 25.00	\$ 175.00	\$ 50.00	\$ 350.00	\$ 50.00	\$ 350.00
18	354	LF	INSTALL LINER IN 8 INCH VCP SEWER ON CALLE DE ARBOLES FROM MANHOLE 101-1-17 AND MANHOLE 101-2-11, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 19)	\$ 25.00	\$ 8,850.00	\$ 30.50	\$ 10,797.00	\$ 35.00	\$ 12,390.00	\$ 26.50	\$ 9,381.00
19	13	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON CALLE DE ARBOLES BETWEEN MANHOLE 101-1-17 AND MANHOLE 101-2-11	500-1.1.7(a) (Appendix V, Dwg# 19)	\$ 50.00	\$ 650.00	\$ 25.00	\$ 325.00	\$ 50.00	\$ 650.00	\$ 50.00	\$ 650.00
20	291	LF	INSTALL LINER IN 8 INCH VCP SEWER ON CALLE DE ANDALUCIA FROM MANHOLE 102-1-11 AND MANHOLE 101-3-07, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 29)	\$ 25.00	\$ 7,275.00	\$ 30.50	\$ 8,875.50	\$ 35.00	\$ 10,185.00	\$ 26.50	\$ 7,711.50
21	8	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON CALLE DE ANDALUCIA BETWEEN MANHOLE 102-1-11 AND MANHOLE 101-3-07	500-1.1.7(a) (Appendix V, Dwg# 29)	\$ 50.00	\$ 400.00	\$ 25.00	\$ 200.00	\$ 50.00	\$ 400.00	\$ 50.00	\$ 400.00
22	263	LF	INSTALL LINER IN 8 INCH VCP SEWER ON PASEO DE LAS DELICIAS FROM MANHOLE 83-2-03 TO MANHOLE 83-2-02, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 62)	\$ 25.00	\$ 6,575.00	\$ 30.50	\$ 8,021.50	\$ 35.00	\$ 9,205.00	\$ 26.50	\$ 6,969.50

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
BASE BID SCHEDULE A												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
23	5	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON PASEO DE LAS DELICIAS BETWEEN MANHOLE 83-2-03 TO MANHOLE 83-2-02	500-1.1.7(a) (Appendix V, Dwg# 62)	\$ 50.00	\$ 250.00	\$ 25.00	\$ 125.00	\$ 50.00	\$ 250.00	\$ 50.00	\$ 250.00
24	200	LF	INSTALL LINER IN 8 INCH VCP SEWER ON VISTA DEL SOL FROM MANHOLE 91-5-02 TO MANHOLE 91-5-01, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix V, Dwg# 58)	\$ 25.00	\$ 5,000.00	\$ 30.50	\$ 6,100.00	\$ 35.00	\$ 7,000.00	\$ 26.50	\$ 5,300.00
25	7	EA	RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD ON VISTA DEL SOL BETWEEN MANHOLE 91-5-02 AND MANHOLE 91-5-01	500-1.1.7(a) (Appendix V, Dwg# 58)	\$ 50.00	\$ 350.00	\$ 25.00	\$ 175.00	\$ 50.00	\$ 350.00	\$ 50.00	\$ 350.00
26	1	EA	POINT REPAIR ON 8" VCP SEWER ON VIA PASQUAL, APPROXIMATELY 12 FEET DEEP. REMOVE AND REPLACE 12 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 91-6-10. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg# 1 & 2)	\$ 6,500.00	\$ 6,500.00	\$ 7,107.00	\$ 7,107.00	\$ 7,500.00	\$ 7,500.00	\$ 16,000.00	\$ 16,000.00
27	1	LS	POINT REPAIR ON 8" VCP SEWER ON VIA PASQUAL, APPROXIMATELY 7 FEET DEEP. REMOVE AND REPLACE 8 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 92-5-30. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg# 9 & 10)	\$ 7,000.00	\$ 7,000.00	\$ 4,646.00	\$ 4,646.00	\$ 7,100.00	\$ 7,100.00	\$ 11,750.00	\$ 11,750.00
28	1	LS	POINT REPAIR ON 8" VCP SEWER AND DROP CONNECTION ON VIA PASQUAL, APPROXIMATELY 8 FEET DEEP. REMOVE AND REPLACE 8 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 92-5-31. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg# 9 & 10)	\$ 10,000.00	\$ 10,000.00	\$ 4,646.00	\$ 4,646.00	\$ 9,000.00	\$ 9,000.00	\$ 11,750.00	\$ 11,750.00
29	1	LS	POINT REPAIR ON 8" VCP SEWER ON VIA LOS MIRADORES, APPROXIMATELY 6 FEET DEEP. REMOVE AND REPLACE 6 FEET MAXIMUM LENGTH OF PIPE. POINT REPAIR LOCATION IS APPROXIMATELY 38' FROM MANHOLE 92-5-06. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg# 44 & 45)	\$ 6,500.00	\$ 6,500.00	\$ 3,505.20	\$ 3,505.20	\$ 5,900.00	\$ 5,900.00	\$ 10,500.00	\$ 10,500.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
BASE BID SCHEDULE A												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
30	1	LS	POINT REPAIR ON 8" VCP SEWER ON VIA LOS MIRADORES, APPROXIMATELY 7 FEET DEEP. REMOVE AND REPLACE 4 FEET MAXIMUM LENGTH OF PIPE. POINT REPAIR LOCATION IS APPROXIMATELY 72' FROM MANHOLE 92-5-06. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg# 44 & 45)	\$ 6,500.00	\$ 6,500.00	\$ 3,450.00	\$ 3,450.00	\$ 6,400.00	\$ 6,400.00	\$ 11,000.00	\$ 11,000.00
31	1	LS	POINT REPAIR ON 8" VCP SEWER ON VISTA DEL SOL, APPROXIMATELY 7 FEET DEEP. REMOVE AND REPLACE 8 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 91-5-01. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg# 58 & 59)	\$ 6,500.00	\$ 6,500.00	\$ 4,572.40	\$ 4,572.40	\$ 6,900.00	\$ 6,900.00	\$ 11,500.00	\$ 11,500.00
32	1	LS	POINT REPAIR ON 8" VCP SEWER 242ND ST, APPROXIMATELY 8 FEET DEEP. REMOVE AND REPLACE 10 FEET MAXIMUM LENGTH OF PIPE. LOCATION IS APPROXIMATELY 100' FROM MANHOLE 104-1-09. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#75 & 76)	\$ 7,500.00	\$ 7,500.00	\$ 4,887.50	\$ 4,887.50	\$ 6,400.00	\$ 6,400.00	\$ 13,800.00	\$ 13,800.00
33	1	LS	POINT REPAIR ON 8" VCP SEWER ON 242ND ST, APPROXIMATELY 8 FEET DEEP. REMOVE AND REPLACE 10 FEET MAXIMUM LENGTH OF PIPE. LOCATION IS APPROXIMATELY 228' FROM MANHOLE 104-1-09. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#75 & 76)	\$ 7,500.00	\$ 7,500.00	\$ 5,750.00	\$ 5,750.00	\$ 6,400.00	\$ 6,400.00	\$ 13,800.00	\$ 13,800.00
34	1	LS	POINT REPAIR ON 8" VCP SEWER ON 242ND ST, APPROXIMATELY 8 FEET DEEP. REMOVE AND REPLACE 6 FEET MAXIMUM LENGTH OF PIPE. LOCATION IS APPROXIMATELY 10' FROM MANHOLE 104-1-10. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#75 & 76)	\$ 7,500.00	\$ 7,500.00	\$ 3,505.20	\$ 3,505.20	\$ 6,400.00	\$ 6,400.00	\$ 10,600.00	\$ 10,600.00
35	1	EA	12" DIAMETER TULIP TREE REMOVAL AND ROOTS	300-1.3, 300-1.4 (Appendix V, Dwg#75)	\$ 1,500.00	\$ 1,500.00	\$ 3,125.00	\$ 3,125.00	\$ 3,000.00	\$ 3,000.00	\$ 2,500.00	\$ 2,500.00
36	1	EA	PLANT 15 GAL CRAPE MYRTLE NEW TREE	308-4 (Appendix V, Dwg#75)	\$ 2,500.00	\$ 2,500.00	\$ 1,875.00	\$ 1,875.00	\$ 2,500.00	\$ 2,500.00	\$ 750.00	\$ 750.00
37	2000	SF	PROVISIONAL REMOVE AND CONSTRUCT PCC DRIVEWAY APPROACH	303-5.9, (Appendix V, Dwg#77)	\$ 5.00	\$ 10,000.00	\$ 15.00	\$ 30,000.00	\$ 15.50	\$ 31,000.00	\$ 12.00	\$ 24,000.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
BASE BID SCHEDULE A												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
38	1	EA	PROVISIONAL TREE REMOVAL UP TO 12" DIAMETER AND ROOTS	300-1.3, 300-1.4 (Appendix V, Dwg#77)	\$ 1,500.00	\$ 1,500.00	\$ 3,125.00	\$ 3,125.00	\$ 3,000.00	\$ 3,000.00	\$ 2,500.00	\$ 2,500.00
39	1	EA	PROVISIONAL PLANT 15 GAL CRAPE MYRTLE NEW TREE	308-4 (Appendix V, Dwg#77)	\$ 2,000.00	\$ 2,000.00	\$ 1,875.00	\$ 1,875.00	\$ 2,500.00	\$ 2,500.00	\$ 750.00	\$ 750.00
40	128	LF	PROVISIONAL PIPELINE REPAIR ON 8" VCP SEWER ON 242ND ST, APPROXIMATELY 8 FEET DEEP. REMOVE AND REPLACE 128 FEET MAXIMUM LENGTH OF PIPE. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#77)	\$ 250.00	\$ 32,000.00	\$ 270.25	\$ 34,592.00	\$ 210.00	\$ 26,880.00	\$ 170.25	\$ 21,792.00
41	1	LS	POINT REPAIR ON 8" VCP SEWER ON OCEAN, APPROXIMATELY 8 FEET DEEP. REMOVE AND REPLACE 6 FEET MAXIMUM LENGTH OF PIPE. LOCATION IS APPROXIMATELY 8' FROM MANHOLE 104-1-10. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#75 & 76)	\$ 7,000.00	\$ 7,000.00	\$ 3,505.20	\$ 3,505.20	\$ 6,900.00	\$ 6,900.00	\$ 10,600.00	\$ 10,600.00
42	30	LF	PROVISIONAL ITEM FOR POINT REPAIR/REPLACEMENT ON 8" VCP SEWER, INCLUDING, IF NECESSARY, LATERAL SERVICE CONNECTION, APPROXIMATELY 8 FEET DEEP, INCLUDING POST-REPAIR CCTV VIDEO INSPECTION RECORDED TO EXTERNAL HARD DRIVE PRIOR TO PLACING PERMANENT RESURFACING	500-1.1.9, 500-1.2-7	\$ 175.00	\$ 5,250.00	\$ 345.00	\$ 10,350.00	\$ 380.00	\$ 11,400.00	\$ 500.00	\$ 15,000.00
43	30	LF	PROVISIONAL ITEM FOR ADDITIONAL LENGTH OF PIPE TO BE REPAIRED AT POINT REPAIR LOCATIONS UP TO APPROXIMATELY 8 FEET DEPTH	500-1.1.9, 500-1.2-7	\$ 200.00	\$ 6,000.00	\$ 345.00	\$ 10,350.00	\$ 380.00	\$ 11,400.00	\$ 350.00	\$ 10,500.00
44	10	EA	PROVISIONAL ITEM FOR ADDITIONAL MANHOLE CHANNEL/SHELF TO BE REPAIRED WITH RAPID SETTING CONCRETE	500-2.10.2 (Appendix V)	\$ 850.00	\$ 8,500.00	\$ 1,725.00	\$ 17,250.00	\$ 650.00	\$ 6,500.00	\$ 750.00	\$ 7,500.00
45	1	LS	POINT REPAIR ON 8" VCP SEWER ON VIA PASQUAL, APPROXIMATELY 7 FEET DEEP. REMOVE AND REPLACE WYE CONNECTION AND LATERAL APPROXIMATELY 42 FEET FROM MANHOLE 092-5-30. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#8, 9,&10)	\$ 6,500.00	\$ 6,500.00	\$ 4,025.00	\$ 4,025.00	\$ 6,900.00	\$ 6,900.00	\$ 9,500.00	\$ 9,500.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
BASE BID SCHEDULE A												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
46	1	LS	POINT REPAIR ON 8" VCP SEWER ON VIA ALAMEDA, APPROXIMATELY 6 FEET DEEP. REMOVE AND REPLACE WYE CONNECTIONS AND LATERALS APPROXIMATELY 112 FEET FROM MANHOLE 101-1-13. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix V, Dwg#15 &16)	\$ 6,500.00	\$ 6,500.00	\$ 4,025.00	\$ 4,025.00	\$ 5,900.00	\$ 5,900.00	\$ 9,500.00	\$ 9,500.00
47	45	EA	WITH RAPID-SETTING CONCRETE: FILL/REPAIR VOIDS IN UNDERLYING MANHOLE CHANNEL/SHELF, AND REPAIR CHANNEL AND SHELF	500-2.10.2(Appendix V)	\$ 300.00	\$ 13,500.00	\$ 600.00	\$ 27,000.00	\$ 675.00	\$ 30,375.00	\$ 1,200.00	\$ 54,000.00
48	2	EA	PRUNE TREE ROOTS ALONG THE SIDEWALK ONLY AT 103 AND 109 VIA ALAMEDA	300-1.3(Appendix V, Dwg#16)	\$ 750.00	\$ 1,500.00	\$ 1,062.50	\$ 2,125.00	\$ 3,000.00	\$ 6,000.00	\$ 2,000.00	\$ 4,000.00
49	400	SF	REOMVE EXISTING AND CONSTRUCT 3 1/2" PCC SIDEWALK OVER 4" CMB	303-5.13(Appendix V, Dwg#16)	\$ 8.00	\$ 3,200.00	\$ 28.75	\$ 11,500.00	\$ 10.00	\$ 4,000.00	\$ 15.00	\$ 6,000.00
50	10	EA	SURVEY MONUMENTS (PROVISIONAL)	2-9.1	\$ 300.00	\$ 3,000.00	\$ 1,000.00	\$ 10,000.00	\$ 400.00	\$ 4,000.00	\$ 300.00	\$ 3,000.00
TOTAL CONSTRUCTION COST FOR SCHEDULE A					\$	483,100.00	\$	540,486.50	\$	578,324.00	\$	602,002.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
ADDITIVE BID SCHEDULE B												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
1	1	LS	MOBILIZATION		\$ 5,000.00	\$ 5,000.00	\$ 10,000.00	\$ 10,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00
2	1	LS	TRAFFIC CONTROL		\$ 5,000.00	\$ 5,000.00	\$ 3,500.00	\$ 3,500.00	\$ 4,000.00	\$ 4,000.00	\$ 4,000.00	\$ 4,000.00
3	1	LS	BEST MANAGEMENT PRACTICES	7-8.6.2	\$ 2,500.00	\$ 2,500.00	\$ 2,500.00	\$ 2,500.00	\$ 1,000.00	\$ 1,000.00	\$ 2,500.00	\$ 2,500.00
4	330	LF	BORDER AVE ALLEY INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 73-4-11 TO MANHOLE 73-4-03, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#1)	\$ 25.00	\$ 8,250.00	\$ 33.75	\$ 11,137.50	\$ 35.00	\$ 11,550.00	\$ 26.00	\$ 8,580.00
5	11	EA	BORDER AVE ALLEY RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 73-4-11 AND MANHOLE 73-4-03	500-1.1.7(a) (Appendix VI, Dwg#1)	\$ 50.00	\$ 550.00	\$ 25.00	\$ 275.00	\$ 50.00	\$ 550.00	\$ 50.00	\$ 550.00
6	255	LF	CRAVENS AVE ALLEY INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 66-1-19 TO MANHOLE 66-1-16, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#12)	\$ 25.00	\$ 6,375.00	\$ 33.75	\$ 8,606.25	\$ 33.00	\$ 8,415.00	\$ 26.00	\$ 6,630.00
7	12	EA	CRAVENS AVE ALLEY RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 66-1-19 AND MANHOLE 66-1-16	500-1.1.7(a) (Appendix VI, Dwg#12)	\$ 50.00	\$ 600.00	\$ 25.00	\$ 300.00	\$ 50.00	\$ 600.00	\$ 50.00	\$ 600.00
8	241	LF	ZAKON RD INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 85-1-06 TO MANHOLE 85-1-03, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#11)	\$ 25.00	\$ 6,025.00	\$ 33.75	\$ 8,133.75	\$ 33.00	\$ 7,953.00	\$ 26.00	\$ 6,266.00
9	6	EA	ZAKON RD RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 85-1-06 TO MANHOLE 85-1-03	500-1.1.7(a) (Appendix VI, Dwg#11)	\$ 50.00	\$ 300.00	\$ 25.00	\$ 150.00	\$ 50.00	\$ 300.00	\$ 50.00	\$ 300.00
10	296	LF	CALLE MAYOR INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 85-2-05 TO MANHOLE 76-5-25, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#3)	\$ 25.00	\$ 7,400.00	\$ 33.75	\$ 9,990.00	\$ 36.00	\$ 10,656.00	\$ 26.00	\$ 7,696.00
11	11	EA	CALLE MAYOR RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 85-2-05 AND MANHOLE 76-5-25	500-1.1.7(a) (Appendix VI, Dwg#3)	\$ 50.00	\$ 550.00	\$ 25.00	\$ 275.00	\$ 50.00	\$ 550.00	\$ 50.00	\$ 550.00
12	132	LF	CALLE MAYOR INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 85-2-04 TO MANHOLE 85-2-05, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#6)	\$ 25.00	\$ 3,300.00	\$ 33.75	\$ 4,455.00	\$ 30.00	\$ 3,960.00	\$ 26.00	\$ 3,432.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
ADDITIVE BID SCHEDULE B					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
13	1	EA	CALLE MAYOR RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 85-2-04 AND MANHOLE 85-2-05	500-1.1.7(a) (Appendix VI, Dwg#6)	\$ 50.00	\$ 50.00	\$ 25.00	\$ 25.00	\$ 50.00	\$ 50.00	\$ 50.00	\$ 50.00
14	240	LF	CALLE MAYOR INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 85-1-08 TO MANHOLE 85-2-04, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#6)	\$ 25.00	\$ 6,000.00	\$ 33.75	\$ 8,100.00	\$ 30.00	\$ 7,200.00	\$ 26.00	\$ 6,240.00
15	1	EA	CALLE MAYOR RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 85-1-08 AND MANHOLE 85-2-04	500-1.1.7(a) (Appendix VI, Dwg#6)	\$ 50.00	\$ 50.00	\$ 25.00	\$ 25.00	\$ 50.00	\$ 50.00	\$ 50.00	\$ 50.00
16	322	LF	CALLE MIRAMAR INSTALL LINER IN 8 INCH VCP SEWER FROM MANHOLE 82-6-09 TO MANHOLE 82-6-05, INCLUDING POST-INSTALLATION VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.4.9 (Appendix VI, Dwg#8)	\$ 25.00	\$ 8,050.00	\$ 33.75	\$ 10,867.50	\$ 34.00	\$ 10,948.00	\$ 26.00	\$ 8,372.00
17	5	EA	CALLE MIRAMAR RECONNECT EXISTING SEWER SERVICE LATERAL TO LINED SEWER PIPE BY TRENCHLESS METHOD BETWEEN MANHOLE 82-6-09 AND MANHOLE 82-6-05	500-1.1.7(a) (Appendix VI, Dwg#8)	\$ 50.00	\$ 250.00	\$ 25.00	\$ 125.00	\$ 50.00	\$ 250.00	\$ 50.00	\$ 250.00
18	1	LS	GRAMERCY PL POINT REPAIR ON 8" VCP SEWER, APPROXIMATELY 25 FEET DEEP. REMOVE AND REPLACE 8 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 29-4-06. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix VI, Dwg#9 & 10)	\$ 22,000.00	\$ 22,000.00	\$ 13,500.00	\$ 13,500.00	\$ 19,000.00	\$ 19,000.00	\$ 9,000.00	\$ 9,000.00
19	1	LS	BORDER AVE ALLEY POINT REPAIR ON 8" VCP SEWER, APPROXIMATELY 5 FEET DEEP. REMOVE AND REPLACE 6 FEET MAXIMUM LENGTH OF PIPE. POINT REPAIR LOCATION APPROXIMATELY 50' FROM MANHOLE 73-4-03. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix VI, Dwg#1)	\$ 9,000.00	\$ 9,000.00	\$ 3,505.20	\$ 3,505.20	\$ 6,000.00	\$ 6,000.00	\$ 7,100.00	\$ 7,100.00
20	87	LF	CALLE MAYOR SURVEY AS NEEDED, REMOVE AND REPLACE 8" VCP SEWER, APPROXIMATELY 2 FEET DEEP. REMOVE AND REPLACE 87 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 85-1-09 AND 85-1-12. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix VI, Dwg#2)	\$ 205.00	\$ 17,835.00	\$ 258.75	\$ 22,511.25	\$ 220.00	\$ 19,140.00	\$ 315.00	\$ 27,405.00

MISCELLANEOUS SEWER MAIN IMPROVEMENTS AND REPAIRS, CIP NO. I-61/I-149

BID OPENING DATE: December 17, 2014					Bidder #1		Bidder #2		Bidder #3		Bidder #4	
BID NO: B2014-59					Ramona, Inc.		Burtech Pipeline, Inc.		Southwest Pipeline		SND Construction, Inc.	
ADDITIVE BID SCHEDULE B												
Item No.	Est. Qty	Units	Bid Item Description	Spec. Section	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid	Unit Price	Total Bid
21	1	LS	CALLE MIRAMAR ALLEY POINT REPAIR ON 8" VCP SEWER APPROXIMATELY 114' FROM MANHOLE, APPROXIMATELY 6 FEET DEEP. REMOVE AND REPLACE 6 FEET MAXIMUM LENGTH OF PIPE. OST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix VI, Dwg#8)	\$ 6,000.00	\$ 6,000.00	\$ 3,505.20	\$ 3,505.20	\$ 7,500.00	\$ 7,500.00	\$ 7,100.00	\$ 7,100.00
22	1	EA	VIA LE SELVA POINT REPAIR ON 8" VCP SEWER, APPROXIMATELY 7 FEET DEEP. REMOVE AND REPLACE 10 FEET MAXIMUM LENGTH OF PIPE. RECONNECT NEW PIPE TO EXISTING MANHOLE 92-1-31. POST-REPAIR CCTV VIDEO-INSPECTION RECORDED TO AN EXTERNAL HARD DRIVE	500-1.1.9, 500-1.2-7 (Appendix VI, Dwg#13)	\$ 8,500.00	\$ 8,500.00	\$ 4,887.50	\$ 4,887.50	\$ 7,500.00	\$ 7,500.00	\$ 9,000.00	\$ 9,000.00
23	5	EA	WITH RAPID-SETTING CONCRETE: FILL/REPAIR VOID(S) IN AND/OR UNDERLYING MANHOLE CHANNEL/SHELF, AND REPAIR CHANNEL AND SHELF	500-2.10.2 (Appendix VI)	\$ 400.00	\$ 2,000.00	\$ 1,725.00	\$ 8,625.00	\$ 675.00	\$ 3,375.00	\$ 1,200.00	\$ 6,000.00
24	20	LF	PROVISIONAL ITEM FOR ADDITIONAL LENGTH OF PIPE TO BE REPAIRED AT POINT REPAIR LOCATIONS	500-1.1.9, 500-1.2-7 (Appendix VI)	\$ 150.00	\$ 3,000.00	\$ 488.75	\$ 9,775.00	\$ 360.00	\$ 7,200.00	\$ 350.00	\$ 7,000.00
25	5	EA	PROVISIONAL ITEM FOR ADDITIONAL MANHOLE CHANNEL/SHELF TO BE REPAIRED WITH RAPID SETTING CONCRETE	500-2.10.2 (Appendix VI)	\$ 850.00	\$ 4,250.00	\$ 1,725.00	\$ 8,625.00	\$ 675.00	\$ 3,375.00	\$ 1,200.00	\$ 6,000.00
26	80	SF	REMOVE AND CONSTRUCT 4' PCC RIBBON GUTTER	303-5.9, (Appendix VI)	\$ 20.00	\$ 1,600.00	\$ 207.00	\$ 16,560.00	\$ 55.00	\$ 4,400.00	\$ 105.00	\$ 8,400.00
27	3000	SF	REMOVE AND CONSTRUCT PCC DRIVEWAY APPROACH	303-5.9, (Appendix VI)	\$ 5.00	\$ 15,000.00	\$ 20.70	\$ 62,100.00	\$ 16.00	\$ 48,000.00	\$ 10.00	\$ 30,000.00
28	10	EA	SURVEY MONUMENTS (PROVISIONAL)	2-9.1	\$ 300.00	\$ 3,000.00	\$ 1,000.00	\$ 10,000.00	\$ 400.00	\$ 4,000.00	\$ 300.00	\$ 3,000.00
TOTAL CONSTRUCTION COST FOR SCHEDULE B					\$	152,435.00	\$	242,059.15	\$	202,522.00	\$	181,071.00