DOOR SCHEDULE (SEE DOOR NOTES THIS SHEET)

NO.	TYPE	SIZE WIDTH	SIZE HT.	SIZE THICK	CORE	MATERIAL DOOR	MATERIAL FRAME	FINISH DOOR	FINISH FRAME	REMARKS
1	A	3'–0"	7'–0"	1¾"	ALUM/GL	ALUM/GL	ALUM	SATIN–ANOD	SATIN–ANOD	PROVIDE TEMPERED GLASS DOOR PANEL
2	B	3'–0"	7'–0"	1¾"	WD	WD/GL	HM *	SEAL/CLR	PAINT	SELECT D.F. SINGLE LITE FRENCH DOOR w/ TEMP. GLASS; UNDERCUT
3	B	3'–0"	7'–0"	1¾"	WD	WD/GL	HM *	SEAL/CLR	PAINT	SELECT D.F. SINGLE LITE FRENCH DOOR w/ TEMP. GLASS; UNDERCUT
4	B	3'–0"	7'–0"	1¾"	WD	WD/GL	HM *	SEAL/CLR	PAINT	SELECT D.F. SINGLE LITE FRENCH DOOR w/ TEMP. GLASS; UNDERCUT
5	B	3'–0"	7'–0"	1¾"	WD	WD/GL	HM *	SEAL/CLR	PAINT	SELECT D.F. SINGLE LITE FRENCH DOOR w/ TEMP. GLASS; UNDERCUT
6	B	3'–0"	7'–0"	1¾"	WD	WD/GL	HM *	SEAL/CLR	PAINT	SELECT D.F. SINGLE LITE FRENCH DOOR w/ TEMP. GLASS; UNDERCUT
7	B	3'–0"	7'–0"	1¾"	WD	WD/GL	HM *	SEAL/CLR	PAINT	SELECT D.F. SINGLE LITE FRENCH DOOR w/ TEMP. GLASS; UNDERCUT PROVIDE WHITE TRANSLUCENT INNER LAYER

* PROVIDE H.M. FRAMES WITH WELDED CORNERS (2)

(1) (3)

WINDOW SCHEDULE (SEE WINDOW NOTES THIS SHEET)

TYPE	SIZE (WIDTH X HEIGHT)	MATERIAL FRAME	MATERIAL GLAZING	FINISH FRAME	FINISH GLAZING	REMARKS
A	6'–4" x 8'–0" VERIFY	ALUM	DBL	CLR. ANOD.	CLEAR	PROVIDE TEMPERED GLASS PER "WINDOW NOTES" #2
B	4'–0" x 2'–4" VERIFY	WOOD	SGL	WOOD	CLEAR	MATCH EXISTING HIGH WINDOWS SASH & FRAMES

WILLIAM LOYD JONES · ARCHITECT · 723 oceanfront walk · venice, california · TEL 310 392 3995 · FAX 310 392 2857

detail title
DOOR SCHEDULE REVISION
(Sht. A5)

project
TORRANCE BUILDING DEPARTMENT
PERMIT CENTER PHASE II

3301 TORRANCE BOULEVARD
TORRANCE, CALIFORNIA 90503

issue
3 CITY REVISIONS #3 22.OCT.14

date
10-22-14

scale
NO SCALE