



LEGEND:

-  (E) PARTITION WALL TO REMAIN, U.N.O. REMOVE AND REPLACE DRYWALL FINISH AT INTERIOR SIDE ONLY, TYP.
-  EXISTING TO BE REMOVED OR DEMOLISHED, TYP., U.N.O.
-  (E) DOOR AND FRAME TO REMAIN, U.N.O.
-  N.I.C. (NOT IN CONTRACT) AREAS

KEYNOTES:

- 1 REMOVE AND SALVAGE (E) WORKSTATIONS AND FURNITURES.
- 2 REMOVE (E) SWING DOOR AND FRAME SALVAGE AS REQUIRED FOR RE-USE.
- 3 DISCONNECT AND REMOVE (E) ELECTRICAL POWER AND TELE-COMM. DATA OUTLETS WHERE WALLS ARE TO REMAIN, TYP.
- 4 REMOVE (E) VINYL FLOOR AND RUBBER BASE THROUGHOUT THE AREA OF WORK
- 5 DISCONNECT AND REMOVE (E) GAS LINES, CAP WITHIN WALL CAVITY.
- 6 REMOVE (E) COUNTERTOP WITH LOWER AND UPPER CABINETS
- 7 REMOVE (E) UPPER CABINETS/SHELVES
- 8 REMOVE (E) SINK. REMOVE AND CAP WATER AND WASTE PLUMBING LINES.
- 9 REMOVE (E) WALL MOUNTED FIRE EXTINGUISHER
- 10 REMOVE (E) EYEWASH/SHOWER. REMOVE AND CAP SUPPLY, WASTE AND VENT LINES BELOW SLAB OR WITHIN WALL CAVITY.
- 11 REMOVE (E) FLOOR DRAIN, COVER AND LEVEL FLOOR TO MATCH EXISTING CONC. FLOOR
- 12 REMOVE (E) EQUIPMENTS/FUME HOODS, SALVAGE AS REQUIRED.
- 13 REMOVE (E) RECESSED METAL WALL PANEL
- 14 REMOVE (E) POCKET DOOR AND FRAME.
- 15 REMOVE (E) WALL BASE AS REQUIRED, SEE FINISH PLAN FOR EXTENT OF BASE DEMO.
- 16 (E) WALL TO REMAIN. MODIFY AS REQUIRED TO INSTALL NEW GLASS WINDOWS PER PLAN. SEE ELEVATION 1C/A3-0.1
- 17 REMOVE & SALVAGE FINISHED END PANEL FOR REINSTALLATION.
- 18 (E) WORKSTATION CUBICLES TO REMAIN IN OPERATION. PROTECT FROM ANY DAMAGE DURING DEMOLITION & CONSTRUCTION. SEE NOTE #6 BELOW.

NOTES:

1. VERIFY SALVAGE REQUIREMENTS FOR ALL DEMO ITEMS WITH THE TORRANCE POLICE FACILITY AND CITY OF TORRANCE PRIOR TO DUMPING.
2. REMOVE ALL DEMOLISHED MATERIALS AND CLEAN THE AREA OF WORK PRIOR TO START OF CONSTRUCTION.
3. VERIFY WITH THE TORRANCE POLICE FACILITY ALL ITEMS TO BE SALVAGED FOR STORAGE.
4. SEE ELECTRICAL AND MECHANICAL DRAWINGS FOR ADDITIONAL DEMO NOTES AND INFORMATION.
5. ALL EXISTING ITEMS NOT PART OF SCOPE OF WORK SHALL REMAIN AND BE PROTECTED DURING CONSTRUCTION.
6. MAINTAIN SECURITY & DUST PROTECTION BETWEEN (E) WORKSTATION CUBICLES AT REPORTS OFFICE #52 & AREA OF NEW WORK ADJACENT TO CUBICLES. REPORTS OFFICE #52 & SUPERVISOR OFFICE #53 MUST REMAIN IN OPERATION, DUST PROTECTED, & NEEDS TO BE SECURED AT ALL TIMES DURING DURATION OF CONSTRUCTION.



CITY OF TORRANCE
POLICE FACILITY
Torrance, California

Consultants
TETRA-IBI Group
ARCHITECTS & PLANNERS
2535 Wilshire Boulevard, Suite 2800
Los Angeles, CA 90047-2600
PHONE 213-201-1900 FAX 213-201-1907



Drawn by	MM		
Checked by	KS		
Date	09/19/11		
No.	Revision	Date	By
A.	ISSUE FOR REVIEW	11-21-11	
B.	ISSUE FOR PLAN CHECK	12-22-11	
C.	PLAN CHECK RESUBMIT	05-15-12	
A.	ADDENDUM 1	10-26-12	

Project
TORRANCE POLICE DEPT.
New Forensic Science Laboratory

3300 Civic Center Dr.,
Torrance, CA. 90503

Drawing Title
EXISTING & DEMO FLOOR PLAN

Project Number
30257

Scale
AS NOTED

Set

Drawing Number

A1-1.1